



# US LHC Accelerator Research Program

*bnl – fnal - lbnl - slac*


## Accelerator Systems Plan

S. Peggs, BNL  
for LARP Accelerator Systems

US-CERN Committee,  
July 1, 2004



# Organization Chart





# Accelerator System Tasks

Task	LEAD	Support
INSTRUMENTATION		
Tune Feedback	Cameron (BNL)	-
Luminometer	Byrd (LBNL)	-
Abort Gap Monitor/LDM	De Santis (LBNL)	-
ACCELERATOR PHYSICS		
Beam Commissioning	Harms (FNAL)	Drees, Furman
Electron Cloud	Furman (LBNL)	Drees
IR and Beam-Beam	Sen (FNAL)	Furman
Phase 1 Collimation Studies	Drees (BNL)	Sen
Phase 2 Collimator R&D	Markiewicz (SLAC)	Mokhov
Hardware Commissioning	Lamm (FNAL)	Wanderer, Rasson



## Accelerator Systems Summary Budget

FY05 TASK	BNL \$k	FNAL \$k	LBNL \$k	SLAC \$k	Total \$k
Tune Feedback	195				195
Luminometer			395		395
Abort Gap Monitor/LDM			≈ 0		0
Beam Commissioning		80			80
Electron Cloud	55		55		110
IR and Beam-Beam	40	230	40		310
Phase 1 Collimation Studies	75				75
Phase 2 Collimator R&D		50		190	240
Hardware Commissioning	75	210	100		385



# Task Milestones (1)

## Accelerator Systems Milestones

June 25, 2004

	FY04		FY05										FY06							
	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12	1
Tune Feedback				1				2				3				4				
Luminometer				1		2														
Abort Gap Monitor/LDM							1													
Beam Commissioning				1	2			3,4												
Electron Cloud	1			2							3		4				5	6,7		
IR and Beam-Beam			1						2	3					4					
Phase 1 Collimation Studies				1					2			3		4						
Phase 2 Collimator R&D	1							2			3						4			
Hardware Commissioning				1		2					3	4								

### KEY:

Tune Feedback

- 1) Evaluate data from PLL prototype studies in SPS
- 2) Cost and Technical review in early CY05
- 3) Conclude coupling study, write coupling correction report
- 4) Design, fabricate, test, & operate prototype baseband PLL electronics & software in RHIC
- 2006) Construction of digitizer boards for LHC PLL

Luminometer

- 1) 40 MHz performance demonstrated, with required accuracy & sensitivity
- 2) Technical and Cost review: go/no go decision for continued prototype construction
- 2005) Design & Fab of final prototype
- 2005) Deliver engineering design of integration into TAN; Conceptual design for IP2 & 8
- 2005) Evaluate options for performing a radiation hardness test
- 2005) Begin interface to CERN DAQ

Abort Gap Monitor/LDM

- 2007) Commission luminometering in the LHC control room
- 1) Deliver AGM engineering feasibility study white paper




## Task Milestones (2)

Beam Commissioning	<ol style="list-style-type: none"><li>1) TI-8 tests begin</li><li>2) Reduced level of activity in FY05</li><li>3) LHCOP group commissioning plan presented at Chamonix '05</li><li>4) Start defining LARP jobs and names, as participants in CERN planning exercise</li><li>2006) Participate in LHC Injection Test, 2 weeks in 2006 with beam</li><li>2007) Several long-term postings to CERN for machine commissioning</li></ol>
Electron Cloud	<ol style="list-style-type: none"><li>1) Participate in SPS EC experiments and studies</li><li>2) Go/no go agreement (CERN/LARP/RHIC) to install cold EC detector in RHIC</li><li>3) Report on simulated reproduction of measured spectrum &amp; spatial distribution of SPS ECs</li><li>4) Report first cut at defining optimal LHC conditioning scenario</li><li>5) Report on applicability of map simulation technique to LHC</li><li>6) First beam with cold EC detector in RHIC</li><li>7) Report on simulated EC at IR4 diagnostic bench</li></ol>
IR and Beam-Beam	<ol style="list-style-type: none"><li>1) Participate in beam studies of wire-based BBC at SPS</li><li>2) Report on BEAMBEAM3D strong-strong simulations (sweeping beam, emittance growth rates)</li><li>3) Report on dipole &amp; quad first layouts (field quality, beta star limits, energy deposition)</li><li>4) Report on impact of beam-beam on IR design (quad/dipole first, performance limits, BBC)</li></ol>
Phase 1 Collimation Studies	<ol style="list-style-type: none"><li>1) Define code bench marking tests</li><li>2) Report on bench-marking of collimation codes with RHIC beam data loss</li><li>3) Test LHC collimator set-up procedures with RHIC collimation system</li><li>4) Report on accuracy of "cleaning efficiency" simulations, and lessons for LHC</li></ol>
Phase 2 Collimator R&D	<ol style="list-style-type: none"><li>1) Phase II collimator meeting, CERN</li><li>2) Present status report at Chamonix '05</li><li>3) Phase II collimator review, go/no go decision</li><li>4) Hire ME, set up lab &amp; test RC0 (existing prototype)</li><li>2006) Design and build more LHC specific RC1 prototype</li></ol>
Hardware Commissioning	<ol style="list-style-type: none"><li>1) Deliver a hardware commissioning report for FY05 and beyond</li><li>2) Warm fit-up of inner triplet (D1/DFBX/Q3/Q2/Q1)</li><li>3) Participate in installation of 3 IRs, and TAS/TAN in IR1</li><li>4) Begin hardware commissioning efforts (room temp, vac, alignment, initial cool-down)</li><li>2006) Installation support &amp; commissioning of US provided systems; injection/sector test</li></ol>




# Tune Feedback (1)

accelerator operation cycle



b3 (units @ 17 mm)



“Snap-back” is not so fast, but the chromaticity jump is huge ~ 300 units!



## Tune Feedback (2)

### Comments:



- 1) Both **tunes** and **linear coupling** must be under control to get a good handle on the (snap-back) **chromaticities**
- 2) Modeling & experimental efforts essential

### FY05 milestones:

- |                |   |
|----------------|---|
| <b>Oct 04</b>  | Evaluate data from PLL prototype studies in SPS   |
| <b>Jan 05</b>  | <b>Cost and Technical review</b> in early CY05  |
| <b>May 05</b>  | Conclude coupling study, write coupling correction report                                       |
| <b>Sept 05</b> | Design, fabricate, test, & <b>operate prototype</b> baseband PLL electronics & software in RHIC |



# Luminometer (1)





## Luminometer (2)

### Comments:

- 1) How many gas Luminometers? Which IPs?
- 2) LAPAC: "Background rejection?"
- 3) Exception that proves the rule - production?

### FY05 milestones:

- Sep 04 40 MHz performance demonstrated
- Nov 04 Tech. & Cost review: go/no go decision for continued prototype construction
- 2005 Design & Fab of final prototype
- 2005 Deliver engineering design of integration into TAN
- 2005 Evaluate options for performing a radiation hardness test
- 2005 Begin interface to CERN DAQ



## Abort Gap Monitor/LDM (1)

### Comments:


- 1) **Abort Gap Monitoring**
  - Required on day "1"
  - Independent of beam dynamics functionality (LDM)
- 2) "LARP should avoid ownership of a critical device"
- 3) **No additional funding after FY04**
- 4) LARP shifts LDM to a potential future task, if "customer" enthusiasm from LHC and/or US builds ...

### FY05 milestones:

**Dec 04** Deliver AGM engineering feasibility study white paper



# Beam Commissioning (1)





## Beam Commissioning (2)

### Comments:

- 1) No tourists – extended visits fully integrated
- 2) LAPAC: “Close connection to CERN staff is vital”
- 3) LAPAC: “What is the connection between BC and other Accelerator Systems tasks?”
- 4) Little activity in 05, some in 06, lots in 07


### FY05 milestones:

- |        |  |
|--------|--|
| Sep 04 | TI-8 tests begin   |
| Jan 05 | LHCOP commissioning plan presented at Chamonix '05                   |
| Jan 05 | Start defining LARP jobs and names, as participants in CERN planning |



# Electron Cloud (1)

MEC vs CSEC results



One of several areas of activity: Maps

LEFT: A map based simulation (MEC) mimics a conventional simulation (CSEC)

6 orders of magnitude speed up

Applicable to LHC?



## Electron Cloud (2)

### Comments:

- 1) RHIC performance limited by pressure rise from WARM electron cloud in field free regions
- 2) LHC cares about heat load from COLD EC, in field
- 3) LAPAC: "Very attractive, but too many dimensions – specialize on experiments ..."



### FY05 milestones:

- |        |   |
|--------|---|
| Jun 04 | Participate in SPS EC experiments and studies       |
| Sep 04 | Go/no go to install cold EC detector in RHIC        |
| Apr 05 | Report on simulated reproduction of SPS ECs         |
| Jun 05 | Report first cut at optimal conditioning scenario   |
| Sep 05 | Report on applicability of map simulation technique |
| Oct 05 | First beam with cold EC detector in RHIC            |
| Oct 05 | Report on simulated EC at IR4 diagnostic bench      |



# Interaction Region & Beam-Beam (1)

QUAD first or DIPOLE first? LARP & CERN continue to consider both ...





## Interaction Region & Beam-Beam (2)

### Comments:

- 1) This task supports Superconducting Magnets tasks
- 2) LAPAC: "Wire Beam-Beam Compensation should be actively pursued"
- 3) Energy deposition component interacts with both magnets and with collimation tasks

### FY05 milestones:


- |        |  |
|--------|--|
| Sep 04 | Participate in beam studies of wire BBC at SPS |
| Feb 05 | Report on BEAMBEAM3D strong-strong simulations |
| Apr 05 | Report on dipole & quad first layouts          |
| Aug 05 | Report on impact of beam-beam on IR design     |




# Phase I Collimation Studies (1)

1 MJ does a lot less damage than 350 MJ !

Primary tungsten collimator



Secondary tungsten collimator



Helium leak in spool piece





## Phase I Collimation Studies (2)

### Comments:


- 1) Chamonix 04: “(The) complexity of the system is also worrying for (the) operations (group)”
- 2) Strong support and integration from/with R. Assmann & R. Schmidt
- 3) Code validation!

### FY05 milestones:

- |         |   |
|---------|---|
| Sep 04  | Define code bench marking tests                                       |
| Feb 05  | Report on bench-marking of collimation codes with RHIC beam data loss |
| May 05  | Test LHC collimator set-up procedures with RHIC collimation system    |
| July 05 | Report on accuracy of “cleaning efficiency” simulations               |



# Phase II Collimators (1)





## Phase II Collimators (2)

### Comments:


- 1) Dimensions, mass, & DC heat load of Phase II Colls. are **VERY DIFFERENT** from those of NLC design
  - “Just design/test the best performance one can”??
- 2) Synergy with IR&BB, & Phase 1 Collimator Studies tasks
- 3) Mutual trust under construction (eg collaboration data flow)

### FY05 milestones:

- |        |  |
|--------|--|
| Jul 04 | Phase II collimator meeting                                |
| Jan 05 | Present status report at Chamonix '05                      |
| Apr 05 | Phase II collimator review, <b>go/no go decision</b>       |
| Sep 05 | Hire ME, set up lab & test <b>RC0</b> (existing prototype) |
| 2006   | Design and build more LHC specific <b>RC1</b> prototype    |



# Hardware Commissioning (1)





## Hardware Commissioning (2)

### Comments:

- 1) Triplet quadrupoles, separation dipoles, absorbers, ..
- 2) LAPAC: "LARP personnel should be put into LHC line structure"

### FY05 milestones:

- |        |   |
|--------|---|
| Sep 04 | Deliver a hardware comm. report plan for FY05++   |
| Nov 04 | Warm fit-up of inner triplet (D1/DFBX/Q3/Q2/Q1)   |
| Apr 05 | Participate in installation of 3 IRs, & IP1 TAS/TAN                                       |
| May 05 | Begin hardware commissioning efforts<br>(room temp, vacuum, alignment, initial cool-down) |
| 2005   | Installation support & commissioning of US provided systems; injection/sector test        |



## Concluding comments

- 0) **Accelerator Systems fully support Superconducting Magnets** in the “long row to hoe” to the IR upgrade
- 1) LARP's mission is **R&D** (but exceptions prove rules)
- 2) “**Collaborating means giving something up**” (so that everyone wins)
- 3) Challenge is to **integrate** Accelerator Systems tasks into:
  - LHC, with “min pain, max gain”
  - Beam Commissioning
- 4) **FY05 is stable**. FY06 (\$10 million?) & FY07 (turn on) look exciting!
- 5) Receptive to **possible future tasks** - Schottky, Beam-Beam compensation, Long. Density Monitoring, tertiary collimators, ...
  - but current (fixed) resources are already spread thin