



Next Linear Collider – U.S. Collaboration

SLAC – FNAL – LBNL – LLNL

Conventional Facilities - Machine Advisory Committee Review

Agenda - May 11, 2002

Saturday, May 11, 2002

8:30 Executive Session

9:00 Conventional Facilities Overview

V. Kuchler

9:30 Update on Studies of Ground Motion

A.Seryi / V. Shiltsev

→ 10:00 Site Considerations & UAB Update

C. Corvin

10:30 Break



Next Linear Collider – U.S. Collaboration

SLAC – FNAL – LBNL – LLNL

Conventional Facilities - Machine Advisory Committee Review

Conventional Facilities

-

Site Considerations

-

UAB Update



Topics

- ➔ • NLC CA Virtual Construction Progress
- Rough Site Comparison(s)
- Underground Advisory Board Updates



- NLC CA 127 & 135 Construction (virtual)
- Initial Fast Surface Flyovers Completed
- Stop-n-Go Inspection Flights Over-Under-Through the Site(s) will Optimize Alignment & Access where Opportunities are Revealed
- Working in 3D low resolution greyscale
- Dumbed Down to Speed Digital Processing
- Color & High Resolution to be Added Last



Two California Sites

- Site 127

Bored Tunnel Housing in Sandstone Bedrock

- Site 135

Cut & Cover Pre-Cast Housing in Sandstone on Bedrock



Next Linear Collider – U.S. Collaboration

SLAC – FNAL – LBNL – LLNL

Conventional Facilities - Machine Advisory Committee Review



CA 135 Lo-Res Greyscale 3D Hi View - South East




Next Linear Collider – U.S. Collaboration

SLAC – FNAL – LBNL – LLNL

Conventional Facilities - Machine Advisory Committee Review

CA Site 135 Sandstone Cut & Cover - 2D Art View West





Next Linear Collider – U.S. Collaboration

SLAC – FNAL – LBNL – LLNL

Conventional Facilities - Machine Advisory Committee Review



CA 135 Lo-Res Greyscale 3D - Lo View South South East



Next Linear Collider – U.S. Collaboration

SLAC – FNAL – LBNL – LLNL

Conventional Facilities - Machine Advisory Committee Review




CA 135 Lo-Res Greyscale 3D - Near View South West



Next Linear Collider – U.S. Collaboration

SLAC – FNAL – LBNL – LLNL

Conventional Facilities - Machine Advisory Committee Review



CA 127 Digitized Lo-Res Greyscale 3D - Hi View South East




Next Linear Collider – U.S. Collaboration

SLAC – FNAL – LBNL – LLNL

Conventional Facilities - Machine Advisory Committee Review

CA Site 127 Sandstone Bored Tunnel – 2D Art View West






Next Linear Collider – U.S. Collaboration

SLAC – FNAL – LBNL – LLNL

Conventional Facilities - Machine Advisory Committee Review



CA 127 Lo-Res Greyscale 3D - Near View West



NLC CA 127 & 135 Construction status (virtual)

- Installing Tunnels, Ramps, Housings, etc.
- Actual Geography, Geology, Roads, Buildings
- Real Housing and Access Designs

- Select, Position & Optimize Housing Alignment Elevation, and Access
- Drag & Drop Whole Machine





Next Linear Collider – U.S. Collaboration

SLAC – FNAL – LBNL – LLNL

Conventional Facilities - Machine Advisory Committee Review

Inserting 3D Geology Into Model from Plans & Sections







Next Linear Collider – U.S. Collaboration

SLAC – FNAL – LBNL – LLNL


Conventional Facilities - Machine Advisory Committee Review

Inserting Public-Private Surface Parcels





Inserting 3D Structures from First Designs




CA 127 Vertical Access to Beam Tunnel & Support Tunnels



Next Linear Collider – U.S. Collaboration

SLAC – FNAL – LBNL – LLNL

Conventional Facilities - Machine Advisory Committee Review





CA 127 Simple Housing Access



Next Linear Collider – U.S. Collaboration

SLAC – FNAL – LBNL – LLNL

Conventional Facilities - Machine Advisory Committee Review




CA 127 Less Direct Housing Access



Next Linear Collider – U.S. Collaboration

SLAC – FNAL – LBNL – LLNL

Conventional Facilities - Machine Advisory Committee Review




CA 127 Complex 2X Housing Access



Next Linear Collider – U.S. Collaboration

SLAC – FNAL – LBNL – LLNL

Conventional Facilities - Machine Advisory Committee Review



CA 135 C&C Experimental Halls, Access Ramps, Dumps & Muon Spoilers



Topics

- NLC CA Virtual Construction Progress
- • Rough Site Comparison(s)
- Underground Advisory Board Updates



Next Linear Collider – U.S. Collaboration

SLAC – FNAL – LBNL – LLNL

Conventional Facilities - Machine Advisory Committee Review

Rough Comparison Summary of NLC Sites - 05/11/02

Site	Injectors	Strata	Type	Area	Main Linac Layout
CA 135	Remote	Rock	C&C	Rural	1 X Precast Section + 52 KG
CA 127	Remote	Rock	Bored	Rural	2 X Bored Tunnels
IL N-S LD	Central	Rock	Bored	Suburban	2 X Bored Tunnels
IL N-S D	Remote	Rock	Bored	Suburban	2 X Bored Tunnels
IL E-W	Remote	Glacial Till	C&C	Rural	1 X Precast Section + 52 KG
Tesla	Remote	Wet Gravel	Bored	Urban-Rural	1 X Bored Tunnel + ~7/9 Halls



Topics

- NLC CA Virtual Construction Progress
- Rough Site Comparison(s)
- ➔ • Underground Advisory Board Updates



NLC UAB IL Meeting Aug. 3, 2001

J. Cogan, J. Simms (facilitators)

T. Burke, P. Garbincius, S. Holmes, V. Kuchler

NLC UAB Consultants:

- **Dr. Tom O'rourke - Cornell University**
- **Dr. Ed Cording - University of Illinois**



NLC UAB CA Meeting Aug. 8-10, 2001

J. Cogan (facilitator)

A. Seryi, F. Asiri, J. Sevilla, C. Corvin

NLC UAB Consultants:

- Dr. Tom O'rourke - Cornell University
- Dr. Ed Cording - University of Illinois

NLC Attending Consultant:

- Phil Frame - Registered CA Geologist



NLC IL Project Briefing to the UAB

- **NLC Conventional Facilities Overview**
- **Review of IL FY'00 Solution (N/S)**
- **Tour of North Aurora Quarry**
- **Review of NuMI Project**
- **Ground Motion Issues**
- **Review of IL FY'01 Solution (E/W)**



NLC CA Project Team Briefing to the UAB

- NLC Machine Overview
- CA Geology
- CA Sites
- CA Sites & Construction Techniques
- Beam Stability
- Structural Stability
- Cooling Vibration Stability
- File Cabinet & Kitchen Sink (held back nothing)



UAB First Recommendations

1. Land Research
2. Drilling Samples & Tests
3. Environmental
4. Ground Motion

Progress Made on ALL 4 !



Start “Bottom’s Up” Land Research

- Private Lands
- State & Federal Lands

(parcel maps w/alignment(s) completed!)



Obtain California Field Data Now !

(same as Snowmass T6 report)

(all require drilling-testing)

Core & Packer Tests,

Weathering Depths,

Water Sampling, w/Logging

Shale & Claystone Expansiveness

Evaluate Long Term Stability

TBM-Liner Squeezing, Face Raveling

C&C Heave, & More



Drilling Status (halted, March '02)

- Well Data Researched
- Drilling Plans-Specifications Reviewed (twice) & Complete

- Owners Contacted
- Drillers Contacted



UAB First Recommendations

1. Land Research
2. Drilling Samples & Tests
- 3. Environmental
4. Ground Motion

Progress Made on ALL 4 !



Add

- Environmental Specialist
(geo-enviro tech hire)
 - Creek Crossings (over & under)
 - Ground Water Management
 - Much Much More
- Tunnel Construction Specialist



Establish & Evaluate Environmental Impact Perimeter Choices

- Have Added Licensed Geo-Enviro Tech to NLC Conventional Facilities Team
- Identify Alignment & Perimeter Choices Framed Against Potential Environmental and Public Impact



Environmental Impact Perimeter

- Draft First Outline Summary of NLC Data prior to Launching an NLC EA/EIS
- Evaluate Adjacent CA EA/EIS Progress CA Dept. of Water & Power Reservoir



- **Geophysics**
 - **Ground Motion Monitoring**
(sites 127,135 data taken)
 - **Model for Tunnel Vibration and Supporting Field Work**
(DMJM Proposal Tunnel-Tunnel Vibration)



Next Linear Collider – U.S. Collaboration

SLAC – FNAL – LBNL – LLNL

Conventional Facilities - Machine Advisory Committee Review

Conventional Facilities

-

Site Considerations

-

UAB Update

END



Next Linear Collider – U.S. Collaboration

SLAC – FNAL – LBNL – LLNL

Conventional Facilities - Machine Advisory Committee Review