



# Results from Structure Fabrication at Fermilab

---

Nikolay Solyak  
Fermilab  
Technical Division



# Outline

---

- Status of ongoing work
- Progress in FXA-002/3 vs. FXA-001
  - ❑ Cell tolerances
  - ❑ Mechanical QC, straightness
  - ❑ Automation of RF Quality Control  
and structure tuning
  - ❑ Coupler calculation and re-design  
for FXA-003
- Schedules and future plans
- Summary



# NLC R&D Project: Mission Goals

---

- X-Band Structure Development
  - RF Design and Analysis
- Manufacture Structures in Support of 8-Pack Test
  - RF Testing
  - Production Methods
- Develop Girders in Support of 8-Pack Test  
(Harry Carter presentation)

- Industrialization of X-Band Structure Production



# Status of Ongoing Work: X-Band Structures Development

---

## – **RF Design Work**

- Have Acquired Software and Hardware to Facilitate RF Design and Analysis
- Have Worked to More Fully Understand the Relationship Between Component Mechanical Design and Electrical Performance

## – **RF Testing**

- Have Developed Single Cell, Bead Pull, and Plunger RF Measurement Hardware and Have Automated the Measurement Process Using LabView

## – **Production Methods**

- Have Conducted Brazing Studies to Optimize Present Joint Design
- Continuing to Develop the Component Cleaning Process
- Continuing to Develop Relationships with Component Parts Suppliers
- Will be Conducting Diffusion Bonding Studies in the Near Future
- Development of Fixturing and Tooling to Facilitate Structure Assembly

(Borrowed from Harry Carter)



## Status of Ongoing Work: X-Band Structures Production



Two **FXA-001/2** structures are built, measured and tuned at Fermilab. First structure took a little more than 9 months, second – 2.5 months. Target is one structure per month.

We are in the process of producing **FXA-003** and **FXB-001** (thru 003). Both currently delayed due to lack of receipt of Large Vacuum Furnace from AVS.

- **FXA** is 20 cm long,  $3\pi/2$  structure, made according to SLAC's design of T20VG5 (5% group velocity).
- **FXB** is 60 cm long,  $5\pi/6$  structure with 3% group velocity, made for NLC High Gradient Testing.




# Cells and couplers production.




## ❖ Parts:

- ❑ 45 mm (61mm) disks from *LaVezzi* and *MedCo*. Disks are not diamond turned ... they are high precision conventional turned This is important for keeping the cost down for the main linac.
- ❑ Couplers from Contour Manufacturing & Metrology Inc. (CMM), *Owen, Gehard (FXB)*.
- ❑ Other Peripheral Components (flanges, water tubes...) from various outside vendors.



CMM coupler, cell is diamond turned







# Progress in FXA-002/3 vs. FXA-001

FXA-001 built in Sept.2001. Lessons from this structure help us to improve production of the next FXA and FXB structures.

- ❑ Decreasing systematic and random errors in disk dimensions (both Lavezzi and MedCo disks) Systematic error 20 MHz  $\rightarrow$  2 MHz
- ❑ Structure straightness improved (Stack assembly and brazing in carbon V-block)  $\rightarrow$
- ❑ Etching process (improving finish cavity surface).
- ❑ Automation of RF QC (Single disk, plunger, bead-pull)
- ❑ Output Coupler design improved (FXA-003)

Fixture with precise carbon V-block





# FXA-001 Disk Specifications

❑ *Conventionally machined disks, tolerances  $\pm 5 \mu\text{m}$  ( $\pm 4.5 \text{ MHz}$ )*


## FXA-001 RF DISK

### RF Disk Frequency Dependency

$\Delta(f) \setminus \Delta(b) = -1.18 \text{ MHz/micron}$

$\Delta(f) \setminus \Delta(a) = +0.5 \text{ MHz/micron}$

$\Delta(f) \setminus \Delta(t) = -0.14 \text{ MHz/micron}$








FXA=003 tolerance in (2b) is:  $-0, +0.010 \text{ mm}$

T. Arkan, 10/10/01





# Tolerances improvement in LaVezzi and MedCo disks.







LaVezzi  
*Random Errors*  
 $\pm 5 \rightarrow \pm 4 \text{ MHz}$   
*Systematic Errors*  
 $- 3 \text{ MHz} \rightarrow ?$

MedCo  
*Random Errors*  
 $\pm 2 \text{ MHz}$   
*Systematic Errors*  
 $-20 \rightarrow -4 \text{ MHz}$



# Errors in disk sets for FXA-003



Tolerances  
better than in  
FXA-001

■ Systematic  
error almost  
removed

■ Random  
Lavezzi  
4.5-5 MHz

Medco  
3 MHz





NLC Req.

Random  
 $\pm 3$  MHz rms

Systematic  
1 MHz



# Production tolerances of FXB-001 structure






# Mechanical Measurements of Structure

- Measurements Conducted
  - Structure Straightness
  - Perpendicularity of I/O Couplers to Disk Stack
  - Parallelism of I/O Coupler bodies to cover plates
  - Beam tube concentricity to Disk Stack
  - RF flange perpendicularity to coupler body
  - Rotational alignment of couplers to one another
  - Multiple leak checks

FXA-001 Setup for Mechanical QC at Fermilab Technical Division




(Tug Arkan)



## Straightness QC on structure

Straightness FXA-001 is shown below. In new fixture FXA-002 stack was aligned and brazed in carbon V-block. Measured straightness 20  $\mu\text{m}$  follows the straightness (bow) of V-block. In final structure about 20  $\mu\text{m}$  jump between stack and coupler cells was found. It should be fixed on FXA-003.







# RF Quality Control

---

Developed few automated set-ups for RF measurements at different stages of structure production


- ❑ Single disk and group of disks
  - New automated set-up
- ❑ Unbraze/Braze Disk Stack Plunger
  - Cells and group of cells frequencies
- Braze Assembly Bead Pull
  - Including Structure Disk Tuning
- ❑ Vertically pulled plunger
  - (coupler tuning using Kahl method)




## RF Quality Control (Disk measurement)

### Automated Contact Set-up.

- Easy to install disk / set of disks. Fixed pressure.
- Automated search and reading own frequencies, Q's (0 - mode,  $\pi$ -mode and two first dipole modes)
- Collecting, plotting and saving all data in Excell file.
- Temperature stabilization in room, humidity and air pressure are controlled (not automated).
- Master disks for reference.
- 0.5-1 minute/per disk








(From G.Romanov)






# RF Quality Control (Plunger measurements)





# RF Quality Control (Bead-pull measurements)



## Features

- ☐ Network Analyzer and step-motor are controlled by computer (LabView).
- ☐ Bead pull support
- ☐ Pulley
- ☐ Automated Reading data from NetAnalyzer.
- ☐ Data acquisition, analysis, plotting, saving
- ☐ Calculation of field and phase distribution, reflection from the cells and couplers.
- ☐ Automation of structure tuning process.


(Temir Khabiboulline)






# Tuning of FXA-002 Structure


FXA-002 structure was measured and tuned after assembly using automated bead-pull set-up. Plot of complex  $S_{11}$  parameter are shown before and after cells tuning. Output coupler was tuned first. E-field distribution on structure axis measured after final tuning is shown below.



$S_{11}$  before cell tuning




$S_{11}$  after tuning








## Simulation and optimization of Couplers for FXA Structure.



FXA structure are made according to SLAC's design of T20VG5 (5% group velocity). It is tapered  $2\pi/3$  structure about 20 cm long, made of 20+3 cells


According to design, output coupler has one neighbor cell with radius  $b_n$ . HFSS model have two identical (output or input) couplers with the same neighbor cell + 3 middle cells. All middle cells have geometry corresponding cell #20 (for output coupler model) or cell #1 (for input coupler).



Target is to get small reflection from coupler and reduce E-field in coupler cell.

Variable parameters in simulations are  $b$ ,  $b_n$ ,  $w$ ,  $a$

HFSS model of coupler  
(one quarter)



- $b$  - outer radius of coupler cell,
- $b_n$  - outer radius of cell neighboring to coupler
- $2w$  - slot width between coupler cell and WG
- $a$  - iris radius between coupler and neighbor cells





(I.Gonin, T.Khabiboulline)



# Output coupler. HFSS simulations.

Designed coupler not matched. By linear combination of basic vectors (dashed lines) reflection from the coupler can be compensated (last three lines in table).


- ❑ Coupler with designed dimensions. Reflection  $S_{11} = 0.05$ .
- ❑ Reflection is compensated by changing cell frequencies  $\Delta b = 12\mu\text{m}$ ,  $\Delta b_n = 1\mu\text{m}$ , how we doing while tune coupler experimentally. E-field in coupler higher than in structure.
- ❑ Increasing coupling slot(w) and iris diameter(a) allowed to reduce E-field in coupler cell.






## E-field distribution in tuned structure

Final E-field distribution of tuned FXA-002 structure shows a good agreement with HFSS simulations.



For tuned FXA-001 structure the E-field in coupler cells is lower. It can be explained by errors in iris shape in regular cells (50 $\mu$ m smaller effective iris diameter), while irises in input and output couplers were made by CMM without such error. It reduce cell-to-cell coupling and E-field in coupler cells.





# Schedules and FY'02 plans

---

## ➤ Complete Large Vacuum Furnace.

- Test, shipment, commissioning. Operational 07/2/02

## ➤ Complete FXA-003. Finish 08/1/02.

- 20 cm long, conventional machined, high gradient, 45 mm OD

## ➤ Make FXB-001 thru 003.

- 60 cm long, conventional machined, high gradient, 61 mm OD
- 001- Finish 8/1/02, shipment to SLAC 8/7/02
- 002/3 (24.5days) Arrives to SLAC by the end of August, 2002.
- High gradient test at SLAC FXB-001 Aug-Dec. FXB-002/3 Jan-Mar,2003

## ➤ Start to order parts for FXC.

- Close to Final NLC Main Linac Design
- 60/90 cm long, assume diamond turned, real accelerators
- Note: Need FXC design (including couplers) by July 2002 in order to deliver all structures to the 8 Pack test by December 2003



## Future Plans: NLC in TD for FY03

---

In FY03 (need ~\$3.3M to accomplish items below  
---if flat funded, we just can't do it!):

- Make FXB-004 thru 009 (plus two extras)
  - Assume better coupler design than we had in FY01.
- Make FXC-001 thru 009 (plus two extras)
- See how many we actually have in mid to late FY03 and decide what to do in FY04
  
- Finalize NLC Girder Design and Make One (or two) for Installation in NLCTA

(from H.Carter)





# Summary

---

- Two FXA-001&2 Structures built, measured and tuned at Fermilab.
- Developed hardware and software for precise RF QC and structure tuning.
- Improved cell tolerances and straightness of the structure.
- FXA-003 and FXB-001 thru 003 are under process of production.