

US LHC Accelerator Research Program

Brookhaven – fermilab - berkeley - stanford

BNL: Accelerator Physics and Beam Commissioning Status and Plans

Accelerator Physics

Collimation Studies

e-cloud


Beam commissionig

beam time at SPS

luminosity monitor commissioning (?)

Budget/FTEs FY05&06

Studies



pressure at coll.

beam current


coll. pos. horiz. & vert.

Beam is scraped away using collimators as scrapers. BLM data is

ring (Inj.)

Losses in the yellow ring (Au)


Zoom into collimator area



Data taken in a "beam experiment" shift to tune simulation software.

More data available at storage energy and various species (Au d n)

New Collimation System




The positions in [m] from the IR are:

| | - J | |
|----------------|------------|-----------------------------------|
| primary | 41.2 | position PD 1m downstream of |
| 1. secondary H | 51.1 | collimator (or as much downstream |
| secondary V | 57.3 | as possible) |
| 2. secondary H | 58.3 | as possible, |


HIC/LHC needs multiple collimator control on the ramp/during the store

RHIC: e-clouds!


IIIII UII UII UI



Vacuum and pressure rises are THE current luminosity limitation at RHIC



2002/2003



55/110 bunches;

Au limit: 4·108 Au⁺/bunch

p limit: 1·10¹⁰ p/bunch

110 bunches;


Au limit: 6.5·10⁸ Au⁺/bunch

d limit: >5.10¹⁰ d/bunch

 $B_{ut \, no} \, ED$ $In \, Yi10...$


Electron Detectors installed at RHIC

- •11 BNL ED
- •1 Micro Channel Plate
- •4 SNS ED
- •1 ANL ED



Some cases


- •NO ELECTRON CLOUD SIGNAL HAS BEEN DETECTED SO FAR
- •The ED acts as a button pick-up that sees the **image current** of the bunch. The signal is inversely proportional to the bunch length.



Signal produced by 1.5 Au-trains of 110 bunches.


Zoom of 4 bunches

during a store in STAR and PHOBOS



Evolution in store is very different (?). Causes unacceptable backgrounds in PHOBOS and high trigger rates in STAR

- Feb 25




Base pressure keeps increasing if we run just at the vacuum limit!

Electron Yields

At RHIC we have pretty much all (bad) materials present:


Electron fluxes to the beam pipe wall for the different IR materials for nominal RHIC conditions: $N_b = 10^9 Au^{79+}$ and 55 bunches.

| material | SEY | E_{max} (eV) | I (mA/m) |
|----------|-----|----------------|----------|
| St St | 1.9 | 310 | 4 |
| ΑI | 2.3 | 300 | 13 |
| Ве | 2.8 | 250 | 30 |



In addition we have a few sections with NEG coating available.


pressure evolution in





Study going on right now:

Try to match predicted background and accidental coincidence rates with measured rates from experiments.

Continuous 212 ns spacing







Simulation predicts significant changes of electron cloud evolution as a function of the fill pattern (at constant total beam currents). In RHIC we can load the machine with a variety of patterns with two spacings (106 ns or 212 ns) and a total between 1 and 110 hunches

Testing/Commissioning

```
Luminosity Monitors (Ion Chambers & CdTe) should/could be shipped to BNL to be tested in RHIC as luminosity monitors: signal/noise reliability accuracy stability (varying conditions etc.)
```

We have one IR (12 o'clock) prepared and ready for equipment testing next pp run in FY05

Propose: one physicist from BNL at CERN for luminosity monitor commissiong at LHC

Beam Commissioning: SPS test beam

| WHAT | WHEN | CERN LIA ISON | |
|--|---------------|-------------------------------|-------|
| | 2004 | | |
| TI8 | | | |
| Materials testing | Sept 04 | R. Schmidt, V. Kain | — BNL |
| Optics matching | Sept 04 | J. Uythoven | |
| | | | |
| SPS | | | |
| Phase Lock Loop | June/Sept 04 | R. Jones | |
| Collimators (& TI8) | Sept 04 | R. Assmann, R. Schmidt | - BNL |
| Ecloud & vacuum diagnostics & studies | Sept 04 | M. Jimenez, F. Zimmerman ◀ | - BNL |
| Impedance & high current tests | ?? Sept 04 ?? | F. Ruggiero, E. Shapashnikova | |
| Long range beam-beam wire compensators | Summer 04 | J.P. Koutchouk | |
| | | | |
| | 2005 | | |
| | 2006 | | |
| Sector test with beam | May 06 | M. Lamont | |
| | 2007 | | |
| | | | |

AP + BC budget "requests"

| | | | FY05 | FY06 |
|-----|----------------|-----|------|------|
| BNL | | FTE | 1.0 | 2.0 |
| | Electron cloud | FTE | 0.5 | 1.0 |
| | Collimation | FTE | 0.5 | 1.0 |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

Summary

- RHIC is currently limited in achievable luminosity by e-cloud/vacuum effects.
- RHIC is the perfect test-bed with all materials: StSt, Al, Be, NEG
- There is some 'horsepower' working on e-cloud already
- The next most prominent issue at RHIC are experimental backgrounds and collimation.
- > RHIC offers loss data with protons and heavy ions (some already available)
- Multiple collimator control schemes can be tested
- > BNL could participate in luminosity monitor testing/commissioning
- Collimator and e-cloud experts will be ready (and trained) to participate in LHC commissioning.