

# FY04, 05 Priorities and Plans BNL Dipole R&D - Update

Michael Anerella  
Superconducting Magnet Division  
Brookhaven National Laboratory  
Upton, NY 11973 USA

# LARP Dipole R&D Priorities

- Finalize magnetic design (previous R. Gupta talk)
- Open midplane mechanical analysis
- Heat transfer analysis – work to follow mechanical analysis (needs new Mohkov data)
- Develop remaining cold mass structure
- Build R&D coils, cold mass
- Base Program work:
  - Cable development
  - 10 turn coils
  - 12T magnet

# LARP Dipole Mechanical Analysis


## Revised Laminated Collar support

### Features:

- Open midplane
- Easy (inexpensive) to build
- Accurate geometry
- Heat absorbed at 80K
- Support bridges minimize coil stress accumulation

### Issues:

- Cable instability
- Deflections
- Secondary 4K heating
- Constrictive '04, '05 Funding (need more \$ for conductor, multiple tests, alternate design, etc.)





# LARP Dipole Mechanical Analysis

## Revised Laminated Collar support (cont'd)

**X - Deflections**

**Y - Deflections**


**max relative deflection ~4 mils**



# LARP Dipole Mechanical Analysis

## Revised Laminated Collar support (cont'd)


### Stresses



# Base Program Support

## Coil Winder Status

- Mechanical Assembly complete
  - wiring underway
  - computer interface underway
- ➡ **operational 3/04**



## FY04, FY05... Plan Summary

### LARP

#### FY04: (\$165K)

- Finalize magnetic design
- complete mechanical analysis and initiate thermal analysis
- Develop external structure to restrain collars

**Iterative  
exercise**

#### FY05: (~\$500K)

- Complete cold mass design
- Complete thermal analysis
- Build R&D coils
- Build “simplified” cold mass

#### FY06:

- Test magnet in cryostat:
  - Quench / field uniformity tests
  - Heat load / temp tests

# FY04, FY05 Plan Summary

## Base Program Support

### **FY04:**

- **Cable Development & testing** (“need to make 1M Nb<sub>3</sub>Sn samples work”)
- **10 turn coil winding**
- **10 turn test magnet assembly & test**
- **12T coil winding**

### **FY05:**

- **12T magnet assembly & test**



# Summary

- **Good progress so far on LARP R&D and Base Program**
- **Lots more to be accomplished in the near term**
- **Continued interaction between mechanical – magnetic design – accelerator folks is crucial**