Draft Acceptance Plan for MQXB

Michael J. Lamm Phil Schlabach Tanaji Sen June 14, 2001

The acceptance plan is a "checklist" which specifies a set of tests on the magnet performed during various stages of the construction. The checklist would have a brief explanation of the test, with reference to an external writeups which would explain the test in detail. Also included would be the acceptable test result. The results of the tests are presented in summary on a form, with reference to full writeups (or a web site) and would be compared with the criteria outlined in the acceptance plan. A draft of this checklist is shown below along with the acceptance form (table 1).

Acceptance Plan

1) Mechanical Twist and Straightness

Reference: table 4 LHC-LQX-ES-0002

Requirement: Less than 1 mR/5 m twist, 100 μm/5 m straightness

Procedure: Traveler

Procedure summary: Warm MQXB is laid on granite table. For twist, Using leveling fixture keyed to Skin alignment key, determine angle of keys relative gravity. For straightness, estimate maximum bow from a straight edge at the horizontal position.

2) Room Temperature Instrumentation and bus work

Reference: Section 3.3 LHC-LQX-ES-0002

Requirement: Each wire and bus properly labeled, proper gauge, not shorted to ground or other wire.

Procedure: Traveler

Procedure summary: As part of the assembly procedure, each wire will be checked against wire list for the above attributes.

3) Room Temperature hipot

Reference: 3.4 Voltage limits LHC-LQX-ES-0002

Requirement: In air or bagged in dry N2, coil to ground/heater and heater to ground/coil can withstand 5 kV voltage difference without breakdown or excessive leakage current. Prior to quadrant busing, voltage from coil quadrant to coil quadrant can withstand 3 kV voltage difference. Coil ringing will be performed on whole coil to look for turn to turn breakdown.

Procedure: Traveler

Procedure summary: Tests performed prior to magnet exposure to Helium gas. Magnet bagged in dry N2. Follow hipot safety procedure outlined in traveler. Quadrant to quadrant (prior to quadrant bussing), 3 kV, Coil: short heater to ground, 5 kV coil relative to ground. Leakage current less than 5 μ A and no breakover. Similar permutation for heater to coil/ground combination. For ringing test, follow safety procedure outlined in traveler. Look for quandrant to quadrant asymmetries and otherwise evidence of electrical breakdown.

4) Cold instrumentation check out

Reference: Section 3.3 LHC-LQX-ES-0002

Requirement: On test stand, instrumentation wires have proper continuity, no shorts to ground

Procedure: Pre test run plan

Procedure summary: All instrumentation wires are checked on the test stand for proper continuity. Resistance to ground is measured.

5) Cold heater checkout

Reference: Section 3.2 LHC-LOX-ES-0002

Requirements: Heater circuits have proper resistance, quenches all quadrants

Procedure: Test plan

Procedure summary: Measure cold resistance. Value equal to 10 ohms. With no magnet excitation current discharge heaters with heater firing units. Using data logger signals verify time contants, no arc over to ground. At 3000 amps, initiate quench with heaters (or manual trip with extraction circuit delay) Verify that there is resistive voltage in all 4 quadrants within 150 ms of heater firing. At 670 amps verify that heater is develop resistive voltage in coils.

6) Cold electrical hipot

Reference: 3.4 Voltage limits LHC-LQX-ES-0002

Requirement: On test stand, in liquid helium, coil to ground/heater and heater to ground/coil can withstand 1.4 kV voltage difference without breakdown or excessive leakage current

Procedure: Pre test run plan

Procedure summary: Follow hipot safety procedure outlined in pretest. Coil: short heater to ground, 1.4 kV coil relative to ground. Leakage current less than 5 $\,\mu$ A and no breakover. Similar permutation for heater

7) No quenching up to and including operating gradient (after training)

Reference: Table 2 LHC-LQX-ES-0002

Requirement: Magnet reaches 230 T/m during first 1.9 K thermal cycle, reaches 220 T/m on 2nd and successive thermal cycles without quenching

Procedure: Run Plan

Procedure summary: During first superfluid test in LMQXB assembly, magnet reaches 230 T/m (12850 amps) as a result of training program. On second thermal cycle the magnet is ramped to 220 T/m (12290 A) without a spontaneous quench

8) Peak temperature and peak voltage to ground.

Reference: Section 3.2 LHC-LQX-ES-0002

Requirement: As a result of a quench, hot spot temperature less than 400 K, Voltage to ground less than 450V.

Procedure: Run plan

Procedure summary: Execute full energy manual trip. At 12 kA (~215 T/m) Power supply is phased back, both heater circuits are energized. No external extraction circuits. Determine the quench integral from the on line data loggers. MIITs value less than 15. If 1/8 taps are available, determine that voltage across each 1/8 is less than 450 volts.

9) No training degradation after full energy deposition trip (see above)

Reference: CERN-KEK-US collaboration minutes

Requirement: Magnet reaches 220 T/m after full energy deposition quench

Procedure: Run Plan

Procedure summary: In superfluid, magnet energy is dissipated through a "full energy deposition quench" This can be accomplished by a 12kA manual trip of the system. The power supply is phased off, the heaters are fired. There is no energy extraction circuit. Then magnet is ramped to 220 T/m without quench.

10) Integral Field

Reference: Table 1 LHC-LQX-ES-0002

Requirement: Integral field variation is less than 1.5×10^{-3}

Procedure: Run Plan

Procedure Summary: Using single stretched wire determine the integral G.dl. at 6 kA excitation current. Compare results to previous magnets.

11) Transfer function

Reference: Table 2, Figure 3 LHC-LQX-ES-0002 Requirement: Gradient /excitation current correlation

Procedure: Run plan

Procedure summary: During cold testing of LMQXB assembly, measure the field strength using the single stretch wire system, at 11.3 kA or 205 T/m. Current to reach 205 T/m should be within 100 amps of Functional specification value.

12) Integrated Cold Harmonics

Reference: Table 3 LHC-LQX-ES-0002 and Integrated Cold Harmonics Acceptance Table

Requirements: Harmonics fall within acceptance table limits.

Procedure: Run plan, attached table 2

Procedure summary: During cold testing, measure harmonics during a continuous ramp cycle up to 12 kA. The up-down average harmonics up to the b10,a10 at 6 kA must fall within acceptance limits. Limits are defined as db + 3 s(b)

Criterion	Short Description	Reference	Accept?	Comment
	Tolerance of 1 mR/5m in twist,		·	
1 Mechanical twist and straightness	100 μm/5 m in straightness	Traveler		
	Room temperature check of each			
	instrumentation wire. Each wire			
	properly labelled, goes to			
	appropriate location, not shorted to			
2 Room temp. Instrumentation and bus	ground, not shorted to another wire	Traveler		
	Room temp. N2 gas 5kV coil to			
3 Room Temperature Hipot	ground	Traveler		
· · · · · · · · · · · · · · · · · · ·		MTF		
	On test stand, each wire is checked	checkout		
4 Cold Instrumentation	for continuity and shorts to ground	procedure		
	, ,	MTF		
		checkout		
5 Cold heater checkout	Heaters adequately protect magnet	procedure		
		MTF		
	In liquid helium Coil to ground, Coil	checkout		
6 Cold electrical Hipot	to heater, heater to coil 1.4 kV	procedure		
	On first thermal cycle magnet is	p		
	trained to 12850 amps.On second			
After training, magnet reaches 220	thermal cycle, magnet reaches			
7 T/m without quench	12300 amps without quench	Run plan		
4		Total promi		
	On second thermal cycle, manual			
	trip QDC,measurem MIITs compare			
	to expected value (corres to <400K.			
	Volts less than 450 V to ground			
8 Peak temp. and voltage to ground	(only do with 1/8 coil taps)	Run plan		
o r dan temp. and venage to greate	On second thermal cycle, after	rtan plan		
	12kA trip with heater firings,			
No training degredation after full	magnet reaches 12300 amps			
9 energy deposition	without quench	Run plan		
3 energy deposition	AT 6kA determine integral G*dl	rtuii piaii		
	should be within 0.15 percent of			
10 Integral Field	•	Run plan		
10 integral i leiu	average	Tall plail		
11 Transfer function	Proper transfer function at 205 T/m	Run plan		
	At 6 kaA cold measure field	Run plan,		
	harmonics compare to harmonics	harmonics		
12 Integral Harmonics	acceptance table	table		
=		1-2	1	

Table 1 MQXB Acceptance Form

n	acceptance band		
	low	high	
b3	-1.66	1.66	
b4	-1.25	1.25	
b5	-0.65	0.65	
b6	-0.76	1.18	
b7	-0.12	0.12	
b8	-0.08	0.08	
b9	-0.04	0.04	
b10	-0.05	0.04	
a3	-1.34	1.34	
a4	-1.29	1.29	
a5	-0.65	0.65	
a6	-0.22	0.17	
a7	-0.11	0.11	
a8	-0.05	0.05	
a9	-0.04	0.04	
a10	-0.04	0.04	

Table 2 Acceptable range of integral harmonics at 6 kA for MQBX (Harmonics Acceptance Table)